

DNIT

Tender Inviting Authority: President , RWA , AWHO (Harbhajan Vihar), 114 sector Mohali (Pb)

Name of Work: Repair to Swimming Pool tiles, drain, fountain ,GI pipe inlets, Pumping machinery . Etc in AWHO (Harbhajan Vihar) sectro 114, SAS Nagar Mohali (Pb)

Contract No: CA No. AWHO/HV/ / 25-26 dated

Bidder Name :

SCHEDULE OF WORK / ITEM(S)

Sl. No.	Item Description	A/U	Qty	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Demolition and Removal of Glass mosaic tiles in the swimming pool and deck area. Including disposing off out of society at own disposal.	Sqm	723.00			
2	M/L PCC 1: 1.5 :3,in floor where required incl two coats of water proof chemical applied diagonally as directed by Engr-in-Charge. Make - Dr Fixit, Pidilite	Sqm	100.00			
2	Supply and Fixing of ceramic tiles 30 x 30 cm and 8 mm thick in all colours as per tiles of swimming pool of approved shade fixing in floor with approved epoxy adhesive, tile joint filling and epoxy grout. Including necessary surface preparation, bedding for laying of tiles, cleaning, waterproofing and fixing of tiles in proper line level complete as per direction of Engr-in -charge /RWA. Make – KAJARIA / SOMMANY /JOHNSON	Sqm	537.00			
3	Supply and Fixing of ceramic tiles 30 x 30 cm and 8 mm thick in all colours as per tiles of swimming pool of approved shade fixing in Wall/dado with approved epoxy adhesive, tile joint filling and epoxy grout. Including necessary surface preparation, bedding for laying of tiles, cleaning, waterproofing and fixing of tiles in proper line level complete as per direction of Engr- in -charge /RWA. Make – KAJARIA/SOMMANY/JOHNSON	Nos	186.00			
4	Supply and fixing of water inlet pipe of UPVC with nozzles at interval of 1.50 meter centre to centre (As per existing sample) in floor of the swimming pool as per direction of Engr- in -charge /RWA	Rmt	75.00			

5	Repair of surface drain along with the swimming pool including levelling to receive the water from the pool as per direction of Engr- in -charge /RWA	Sqm	60.00				
6	Dismantling/ refixing of underwater light in swimming pool as per direction of Engr- in -charge /RWA	Nos	16.00				
7	Dismantling/ refixing of underwater light in fountain nozel wall etc in swimming pool as per direction of Engr- in -charge /RWA	Nos	19.00				
8	Replacement of defective drain covers along the swimming pool.	Rmt	90.00				
9	Repair of sand stone stone on open space and filling pigment in joints at various place as per direction of Engr- in -charge /RWA	Rmt	200				
10	Supply and fixing of Pumping machinery in fountain of suitable size, discharge and head so that the min height of water sprinkling from water level should be 1.20 mtr high. Location are as under, where Pump reqd to fix after tiling and other work :-						
	CC-I fountain near Gate No I	Nos	1				
	CC-II near Inside Gate	Nos	1				
	CC-II near out Gate	Nos	1				
	CC-II behind the GSD canteen	Nos	1				
	Total of BOQ Rs.						
	Total in Figures						

SIGNATURE OF BIDDER/ FIRM DULY STAMPED

DATED: